

**PART 1 – GENERAL**

- 1.1 A three output Harmonic Mitigating Isolation Transformer (HMT) with efficiency per NEMA Std. TP-1 over a wide load range and designed to eliminate the harmful effects of all the low frequency, odd order harmonic currents from the 3<sup>rd</sup> through 15<sup>th</sup>:**
- .1 Transformer efficiency shall satisfy requirements at not just 35% load as required by NEMA Std. TP-1, but also over the operating range from 35 to 65% load.
  - .2 Treatment of triplen (3<sup>rd</sup>, 9<sup>th</sup>, and 15<sup>th</sup>) harmonic load currents: Secondary winding configuration must cancel fluxes due to zero sequence harmonic currents without coupling them to the primary winding.
  - .3 There shall be three outputs per phase, with the appropriate phase-shifts between them to achieve cancellation of the 5<sup>th</sup>, 7<sup>th</sup>, 11<sup>th</sup>, & 13<sup>th</sup> harmonic fluxes within the secondary windings.
  - .4 Harmonic mitigation shall be by electromagnetic means only. No capacitors or electronics shall be used.
  - .5 Evidence of relevant application experience must be available upon request.
- 1.2 Voltage and kVA Requirements:**
- .1 Primary Voltage: [480][600][optional 208][other] Volts
  - .2 Secondary Voltage: [120/208][other] Volts
  - .3 Input kVA rating: [15][30][45][75][112.5][150][225][300][500][other] kVA
  - .4 Rating of each output as percent of input rating: 40%
  - .5 System Frequency: 60 [50] Hertz
- 1.3 Submittals:**
- .1 Submit specifications, data sheets, dimensional drawings, non-linear test program description and sample test report for approval before manufacturing.
  - .2 Submit certified copies of the standard production tests required by NEMA standards ST-20 and TP2 for each transformer for approval before shipment.
  - .3 Submit certified type test results for linear load efficiency from 35 to 65% load for each size of transformer ordered on the project for approval before shipment.
  - .4 Do not commence manufacturing or shipping without the appropriate technical approval from the engineer and scheduling approval from the purchaser.
- 1.4 Applicable Standards (Latest Edition):**
- .1 NEMA ST-20 – Dry Type Transformers for General Applications
  - .2 NEMA TP1 – Guide for Determining Energy Efficiency for Distribution Transformers
  - .3 NEMA TP2 – Standard Test Method for Measuring the Energy Consumption of Distribution Transformers
  - .4 CSA C9 – Dry-Type Transformers
  - .5 CAN/CSA-C802.2 – Minimum Efficiency Values for Dry-Type Transformers

**PART 2 – PRODUCT**

- 2.1 Key Requirements:**
- .1 Three 3-phase outputs with relative phase-shift to cancel 5<sup>th</sup>, 7<sup>th</sup>, 11<sup>th</sup> & 13<sup>th</sup> harmonic currents
  - .2 Positive & negative sequence impedance at 60Hz:  
2.8% to 3.5% (up to 75 kVA), 3.2% to 4.5% (112.5 to 300 kVA), 5.0% to 6.0% (500kVA).
  - .3 Zero sequence impedance and reactance at 60Hz:  $\leq 0.95\%$  and  $0.3\%$  for up to 150 kVA,  $\leq 1.0\%$  and  $0.5\%$  for 225 kVA and 300 kVA,  $\leq 1.5\%$  and  $1.0\%$  for 500kVA.
  - .4 Load compatibility: K factor up to 20, Crest factor up to 4.5
  - .5 Secondary neutral connection rated at 200% of the rated secondary phase current
  - .6 Linear Load Efficiency: Comply to NEMA Std. TP-1 requirement for efficiency at 35% load and for the operating range from 35% to 65% linear load: 97.0% at 15 kVA, 97.5% at 30 kVA, 97.7% at 45 kVA, 98.0% at 75 kVA, 98.2% at 112.5kVA, 98.3% at 150 kVA, 98.5% at 225 kVA, 98.6% at 300 kVA, 98.7% at 500 kVA. Submit for approval before shipment certified type test results for linear load efficiency from 35 to 65% load for each size of transformer ordered on the project.
- 2.2 Basic Requirements:**
- .1 Three-phase, common core construction. Convection air-cooled
  - .2 Copper Windings
  - .3 Insulation Class: 220°C system, (15kVA and 30kVA transformers have 200°C insulation class)
  - .4 Temperature rise: 130°C [115°C] [other]
  - .5 Taps:  $2 \times \pm 2.5\%$  (2FCAN, 2FCBN) for 30 kVA and larger,  $1 \times \pm 5\%$  for 15 kVA and all 208V primary
  - .6 Sound level per NEMA Std. ST-20: max. 45dB up to 45 kVA, 50 dB from 75 to 150 kVA, 55 dB from 225 to 300 kVA, 60dB for 500 kVA, and 64 dB for 750 kVA.
  - .7 Enclosure: NEMA 3R, ventilated, sprinkler-proof. [Outdoor NEMA3R enhanced][Other]. Colour: Grey
  - .8 Anti-vibration pads shall be used between the core and the enclosure
  - .9 Single electrostatic shield: 60dB attenuation

- .10 UL listed and CSA approved
- .11 Built to NEMA ST-20 and in accordance with all applicable UL, CSA and ANSI/IEEE standards
- .12 Warranty: 10 year pro-rated, with standard limited liability clauses

**2.3 Other Requirements:**

- .1 [OPTION] [Provide with second electrostatic shield.]
- .2 [OPTION] Over-Temperature switch[es] wired to internal terminal strip. Temperatures specified for use with class 220°C insulation systems. Standard configuration is N.C. opening [N.O. closing] on high temperature. Number of switches: [one switch: 170°C or 200°C on center coil] [two switches: 170°C and 200°C on center coil] [six switches: one 170°C and one 200°C on each of the 3 coils]
- .3 [OPTION] Submit for approval before shipment certified production test results with serial numbers for linear load efficiency from 35 to 65% load for one of each size of transformer manufactured for the actual project.

**2.4 Acceptable Product and Manufacturer:**

- .1 HARMONY-3E™ Nema STD TP1 Compliant Harmonic Mitigating Transformer by MIRUS International Inc.
- .2 No alternates or substitutions will be permitted unless they meet all the requirements of this specification, including document submittal requirements, and that they are submitted in sufficient time to receive written approval by the engineer at least 10 days before bid closing.

**PART 3 – EXECUTION**

**3.1 Installation**

- .1 The installing contractor shall install the Harmonic Mitigating Transformer per the manufacturer's recommended installation practices as found in the installation, operation, and maintenance manual and comply with all applicable codes.

**3.2 Acceptance**

- .1 [OPTION] Manufacturer's representative shall visit site, verify installation, and submit to owner a letter stating equipment and installation meets intent of specification and manufacturer's warranties and guarantees are in effect.